

**DESHBANDHU COLLEGE**  
**KALKAJI, NEW DELHI – 110019**

Date: 11.08.2020

**QUOTATIONS FOR COMPOST PIT WORK**

Sealed Quotations are invited for Compost pit work with following specification. The Quotation must be addressed to "The Principal, Deshbandhu College, University of Delhi, Kalkaji, New Delhi – 110019 and reach by 21.08.2020

S No.	Details	Unit	Quantity	Rates
S No	Name of Work	Quantity	Rate	Amount
1	Excavation Work manually / by mechanically means including stacking and disposal of unserviceable material with in 50 Meters lead as per direction of Engineer in charge/ Committee	2 Cub. Mtr.		
2	Providing brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in cement mortar 1:3 (1 Cement : 3 coarse sand) in superstructure for closing cavity 5 to 7.5 cm wide in cavity wall complete with 10 cm / 11.4 cm wide bitumen felt type 3 grade 1.	6.5 Cub. Mtr.		
3	Cement Plaster 12 mm in cement mortar 1:4 etc. work all in respect.	35 Sqr Mtr		
4	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter .(600 mm over all girth)	45 Sqr. Mtr		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	2 Cub Mtr		
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (Fabricated with 40x40x4 mm angel, 6 mm sqr bar )	400 KG		
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (Round/ Squire Pipe size of 75 mm thickness 2 mm)	250 KG		
8	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 11.3.1 40 mm thick with 20 mm nominal size stone aggregate	120 Sqr Ft.		
9	Making plinth protection 50mm thick of cement concrete-1:3:6 (1 cement : 3 coarse sand (zone - III) : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, leveling & dressing & finishing the top smooth.	12 Sqr. Mtr		
	<b>Grand Total</b>			

*Rajw Aggr*

**Terms & Conditions:**

1. The quotations should contain the complete technical specifications.
2. The quotation should be valid for 120 days from the date of submission.
3. The price quoted should include all taxes.
4. The number of items may increase or decrease at the sole discretion of the college.
5. The college reserves the right to cancel/call off any quotation without assigning any reason/s.
6. Payment will be made only after the successful delivery of the work as found satisfactory to the competent authority.

Rajwajj S  
PRINCIPAL 11.08.2020